



PVC-DS PIPE - ASTM D-2729
&
PVC-SEWER PIPE - ASTM D-3034

CNWPVC-6

AUGUST, 2006

PLEASE ORDER BY PART NUMBER.

PVC-DS ASTM D-2729 SOLID & PERFORATED	SIZE	O.D.	MIN. WALL	WEIGHT PER 100'	FEET PER PALLET	PALLETS PER T.L.	PART NO. SOLID	PART NO. PERF.
	3"	3.250	.070	48.22	1000	32	52075	52180
	4	4.215	.075	67.45	900	24	52115	52210
	6	6.275	.100	134.15	350	24	52155	52260

FURNISHED IN 10' LENGTHS BELLED END.

PERFORATIONS ARE 2 ROWS OF 1/2" HOLES ON 5" CENTERS 120° APART.

SOLVENT WELD SDR-35 SEWER PIPE ASTM D-3034	SIZE	O.D.	MIN. WALL	WEIGHT PER 100'	FEET PER PALLET	PALLETS PER T.L.	LGTH.	PART NO.
	4"	4.215	.120	106.51	900	24	10'	53115
					1200	16	20	53118
	6	6.275	.180	238.4	350	24	10	53180
700					12	20	53183	

SOLVENT WELD SDR-35 SEWER PIPE ASTM D-3034 PERFORATED	SIZE	O.D.	MIN. WALL	WEIGHT PER 100'	FEET PER PALLET	PALLETS PER T.L.	LGTH.	PART NO.
	4"	4.215	.120	106.51	900	24	10'	53120
6	6.275	.180	238.4	350	24	10	53195	

GASKET JOINT PSM SEWER PIPE SDR-35 ASTM D-3034	4"	4.215	.120	109.84	1260	18	14'	53726
				108.84	1200	16	20	53735
	6	6.275	.180	245.85	490	18	14	53786
				243.62	700	12	20	53795
	8	8.400	.240	441.75	280	18	14	53806
				436.81	400	12	20	53815

14' & 20' LAYING LENGTHS. INSERTION DEPTH RING IS MARKED ON THE BEVELED SPIGOT END OF PIPE.

GASKETS ARE REINFORCE RUBBER RING AND PERMANENTLY INSTALLED IN AN INTEGRAL BELL.

MADE OF COMPOUNDS CONFORMING TO ASTM D-1784 WITH CELL CLASSIFICATION OF 12454-B.

REFER TO ASTM D-2321 FOR PROPER INSTALLATION PROCEDURES OF SDR-35 SEWER PIPE.

CRESLINE-NORTHWEST, LLC.

CORPORATE HEADQUARTERS: 600 CROSS POINTE BOULEVARD · EVANSVILLE, IN 47715 · TELEPHONE (812) 428-9300

PLANT: 223 MAURIN ROAD · CHEHALIS, WA 98532 · TELEPHONE (360) 740-0708

www.cresline.com